

# C<sup>3</sup> LINAC Demonstration Proposal

Cool Copper Collider Workshop

---

Faya Wang

7 Feb. 2023


# Acknowledgement

---

- **SLAC: Mei Bai , Valery Borzenets , Martin Breidenbach, Anatoly Krasnykh, Carsten Hast, Xianghong Li, Zenghai Li, Emilio Nanni, Tim O’Heron, Dennis Palmer, Thomas Peterson, Alex Ratti, Tor Raubenheimer, Muhammad Shumail, Caterina Vernieri, Glen White, Juhao Wu**
- **Florida State University: Guo Wei, Kourosch Shoele**



# Introduction Staged Approach

- C<sup>3</sup> accelerator technology: Modularized linac based on liquid N<sub>2</sub> cooled C-band cavity.
- Cryomodules (CM)s are vacuum insulated cryostats housing 4 rafts, and ha 75 cm ID and about 9 m long.
- Rafts are mechanical supporting structures consisting of 2 accelerator structures and one quadrupole magnet. They are pre-aligned at warm to 5 microns. Each raft has mechanical actuators to align one raft to the next with 5 degrees of freedom.



# RF Parameters – C<sup>3</sup>250/550 GeV

- At C<sup>3</sup> the same LINAC can deliver 250 GeV c.o.m and 550 GeV c.o.m in 8 km
- The optimized structure can reach 300 MΩ/m at 80K.
- The accelerator beam aperture (diameter) is 5.2 mm.



- Each CM can reach up to 0.7 GeV with 4 X 50MW klystrons .

Gradient (MV/m)	Power diss. (W)	rf flat top (ns)	Pulse compr.	Comments	Power/area (W/cm <sup>2</sup> )	ΔT Cu-bulk to LN <sub>2</sub> (K)
70	2500	700	N	C <sup>3</sup> -250	0.393	2.3
120	2500	250	N	C <sup>3</sup> -550	0.393	2.3
155	3900	250	N	C <sup>3</sup> -550 in 7 km	0.614	2.5
120	1650	250	Y	C <sup>3</sup> -550	0.259	2.1

# RF Parameters – C<sup>3</sup>250/550 GeV

- Main linac cryogenic heat load:

- ~9 MW (C<sup>3</sup>250, C<sup>3</sup>550-8km)  $\frac{250 \text{ GeV}}{70 \text{ MeV/m}} \times 2500 \text{ W/m}$


The LN will cool the accelerator structures by nucleate boiling with the vapor velocity near Cryoplant ~ 3m/s at a power density of 0.4 W/cm<sup>2</sup>.

- ~14 MW (C<sup>3</sup>550-7km)  $\frac{550 \text{ GeV}}{155 \text{ MeV/m}} \times 3900 \frac{\text{W}}{\text{m}}$

Gradient (MV/m)	Power diss. (W)	rf flat top (ns)	Pulse compr.	Comments	Power/area (W/cm <sup>2</sup> )	ΔT Cu-bulk to LN <sub>2</sub> (K)
70	2500	700	N	C <sup>3</sup> -250	0.393	2.3
120	2500	250	N	C <sup>3</sup> -550	0.393	2.3
155	3900	250	N	C <sup>3</sup> -550 in 7 km	0.614	2.5
120	1650	250	Y	C <sup>3</sup> -550	0.259	2.1


# Introduction Staged Approach

- An X-band cryogenic structure has been demonstrated at high gradient.
- The C-band has been tested at low power at SLAC and high power without beam at Radiabeam



# Introduction Staged Approach

- An X-band cryogenic structure has been demonstrated at high gradient.
- The C-band has been tested at low power at SLAC and high power without beam at Radiabeam
- **C<sup>3</sup> Linac Remaining Major Risks**
  - Achievable gradient and stability over C<sup>3</sup> full electron bunch train.
  - Beam emittance growth due to accelerator wakefields
  - Systematic study of alignment and vibration tolerance
  - Performance of the accelerators and the cryostat at the full cryogenic liquid and gas flow rate as expected in C<sup>3</sup>.
  - A reliable cost basis for extrapolation to C<sup>3</sup> scale production.



C<sup>3</sup> Demo will focus on the 5 thrusts:

- ❖ Collider Cryogenics Design Study
- ❖ CryoModule
- ❖ Accelerator Structure
- ❖ Beam Dynamics Experimental Study
- ❖ C<sup>3</sup> Main Linac Beam Dynamics Simulation Study



# Introduction Staged Approach

C<sup>3</sup> Demo will focus on the 5 thrusts:

❖ Collider Cryogenics Design Study


❖ CryoModule

❖ Accelerator Structure

❖ Beam Dynamics

❖ C<sup>3</sup> Main Linac Beam Dynamics

- Vibrations due to boiling of LN
- Large scale simulation setups (from 100s to 100 meters)
- Optimizing CM and cold mass design to avoid the liquid surface turbulent flow
- Engineering procedures to eliminate possible problems from linac warm-up and cold-down process
- Instrumentation needs



# Introduction Staged Approach

C<sup>3</sup> Demo will focus on the 5 thrusts:


❖ Collider Cryogenics Design Study

❖ **CryoModule**

❖ Accelerator Structure

❖ Beam Dynamics

❖ C<sup>3</sup> Main Linac Beam Dynamics




- Adequate stability of the quadrupoles and accelerators during powered operation and full C<sup>3</sup> cryogenics fluid flow rate (with margins)
- Adequate range, precision and bandwidth of the raft positioning systems
- Full C<sup>3</sup> cryogenic flow rate benchmarking with simulation
- In-situ CM vibration measurement
- In-situ pre-beam alignment  $\leq 500$   $\mu\text{m}$
- Tunable permanent quadrupole magnets
- Waveguide transitions into the Cryomodule

# Introduction Staged Approach

C<sup>3</sup> Demo will focus on the 5 thrusts:

- ❖ Collider Cryogenics Design Study
- ❖ CryoModule
- ❖ **Accelerator Structure**
- ❖ Beam Dynamics
- ❖ C<sup>3</sup> Main Linac Beam Dynamics

- Achievable gradient and gradient stability at the C<sup>3</sup> equivalent beam loading
- HOM damping design and fabrication
- Integrated beam position monitor for structure alignment
- Optimization of the mechanical design for structure fabrication and tuning
- HOM detuning design




# Introduction Staged Approach

C<sup>3</sup> Demo will focus on the 5 thrusts:

- ❖ Collider Cryogenics Design Study
- ❖ CryoModule
- ❖ Accelerator Structure
- ❖ **Beam Dynamics**
- ❖ C<sup>3</sup> Main Linac Beam Dynamics

- Measure beam properties and validate wakefield model with simulations.
- Begin development of feedback loops for minimization of emittance growth.
- Develop systematic beam-based diagnostics for different stages of the Demonstrator.



# Introduction Staged Approach

---

C<sup>3</sup> Demo will focus on the 5 thrusts:

❖ Collider Cryogenics Design Study

❖ CryoModule


❖ Accelerator Structure

❖ Beam Dynamics

❖ **C<sup>3</sup> Main Linac Beam Dynamics**

- Perform emittance preservation simulation studies to determine alignment and vibration tolerances
- Investigation and optimization of lattice design, BNS damping, dispersion free steering, and wakefield corrections ect.

# Introduction Staged Approach



# Introduction Staged Approach

---

- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - **Demonstrate the accelerator structure at the full C<sup>3</sup> equivalent beam loading:**
    - **Unloaded and loaded at 70 MeV/m and 700 ns with 190 mA – C<sup>3</sup>250**
    - **Unloaded and loaded gradient of 120 MeV/m and 250 ns with 300 mA - C<sup>3</sup>550**

# Introduction Staged Approach


---

- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - **Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading.**
    - ✓ High current DC injector
    - ✓ HCM Linac




# Introduction Staged Approach

- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - **Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading.**



# Introduction Staged Approach

- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - **Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading.**





- Capture Efficiency = 61 %
- Q<sub>bunch</sub> = 115 pC

**$I_{ave} \approx 330 \text{ mA}$**


# Introduction Staged Approach

- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - **Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading.**




# Introduction Staged Approach

- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - **Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading.**




## ✓ HCM Linac



- 2x50 MW C-band RF station needed to be developed.
- About 10% rf transmission loss
- With structure match to 43% beam loading
  - 4 structure at 78 MeV/m with no beam
  - 2 structure at 111 MeV/m wo beam and 90 MeV/m with 190 mA (C3-250)
  - 1 structure at 157 MeV/m wo beam and 125 MeV/m with 300 mA (C3-550)

# Introduction Staged Approach


- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading at SLAC NLCTA.
  - 2x50 MW C-band rf stations will be developed with repurposing an existing X-band station modulator.
  - The existing S-band station in NLCTA will be used to power the injector.




# Introduction Staged Approach

- Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.



- Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading at SLAC NLCTA.



- $Q=115\text{pC}$ ,  $\gamma\epsilon_{x,y}$  (90%) =  $3.7 \times 3.3 \mu\text{m-rad}$
- 3 pC collimated on HCM aperture ( $r=2.6\text{mm}$ )



- Stage 1 will use NLCTA as it is.



# Introduction Staged Approach


---

- **Stage 2: First Scale-up Demonstration of A C<sup>3</sup> CryoModule Linac**
  - A high brightness photo injector with at least two bunches and various space
  - A large aperture S-band booster linac
  - A full C<sup>3</sup> CM Linac.
- Production of the cryomodule assembly with in-situ pre-beam alignment  $\leq 500 \mu\text{m}$
- Demonstration of the acceleration structure in the full CM LINAC reaching unloaded gradient of 155 MeV/m at 250 ns
- Development of high brightness RF photo injector with an LCLS-like S-band RF gun and an S-band booster LINAC re-using the Stage 1 HCM cryostat
- Evaluation of cryomodule LINAC beam performance in the presence of wakefields, and benchmarking with the beam simulation




# Introduction Staged Approach

- **Stage 2: First Scale-up Demonstration of A C<sup>3</sup> CryoModule Linac**
  - A high brightness photo injector with at least two bunches and variable bunch space
  - A large aperture S-band booster linac: repurpose the stage 1 half CM with 4x1m S-band structures
  - A full C<sup>3</sup> CM Linac.





# Introduction Staged Approach

- **Stage 2: First Scale-up Demonstration of A C<sup>3</sup> CryoModule Linac**
  - 8x50 MW C-band RF station will be built.
  - With zero beam loading and about 10% RF transmission loss
    - 1 klystron per structure: 8 structures at 113 MeV/m
    - 2 klystrons per structure: 4 structures at 160 MeV/m



# Introduction Staged Approach


- Stage 2: First Scale-up Demonstration of A C<sup>3</sup> CryoModule Linac**
  - The preliminary simulation shows a 1nC beam of 2 $\mu\text{m}\cdot\text{rad}$  emittance is possible at a final energy of 1.2 MeV.



# Introduction Staged Approach

- **Stage 2: First Scale-up Demonstration of a Full C<sup>3</sup> CryoModule**
  - **Beam diagnostics at the LINAC end: Long range wakefield and longitudinal short range wakefield**


Quantities	Devices
Energy and Energy spread	Dipole + screen/wire scanner
Charge	Faraday cup and beam dump, toroid
Beam size and beam position	Profile screens/wire scanner and NLCTA Quad package
Emittance and wakefield effects	Coherent undulator radiation and profile screen/wire scanner
Bunch length	Transverse deflecting cavity




# Introduction Staged Approach

- **Stage 2: First Scale-up Demonstration of a Full C<sup>3</sup> CryoModule**
  - **Beam diagnostics at the LINAC end: Long range wakefield and longitudinal short range wakefield**

Quantities	Devices
Energy and Energy spread	Dipole + screen/wire scanner
Charge	Faraday cup and beam dump, toroid
Beam size and beam position	Profile screens/wire scanner and NLCTA Quad package
Emittance and wakefield effects	Coherent undulator radiation and profile screen/wire scanner
Bunch length	Transverse deflecting cavity






# Introduction Staged Approach

---

- **Stage 2:** NLCTA refurbishment will be required.
  
- **Site preparation:**
  - a) The NLCTA bunker enclosure and its roof will be cleaned out.
  - b) The current control racks for the current S-band and the X-band station 0 & 1 will be removed.
  - d) Drilling 11 penetrations on the bunker roof for the C-band RF waveguide, and installation of support structures for the 11 RF stations.
  
- **Utilities:** installation of 480V AC power and low conductivity water (LCW) distribution for 11 RF sources on the NLCTA roof, ventilation for N<sub>2</sub> gas, electronic racks, and cables. 480V power is available from a nearby sub-station. LCW is available from 2 pressure limiting locations inside and outside ESB.

# Introduction Staged Approach

- **Stage 3: Integrated Demonstration Towards the C<sup>3</sup> main LINAC**
  - Cryogenics performance study at the C<sup>3</sup> full flow rate
  - Mapping out of transverse short range wakefield
  - Structure and magnet pre-beam alignment in each CM as well as between through multiple CMs






# Introduction Staged Approach

- **Stage 3: Integrated Demonstration Towards the C<sup>3</sup> main LINAC**
  - Cryogenics performance study at the C<sup>3</sup> full flow rate
  - Mapping out of transverse short range wakefield
  - Structure and magnet pre-beam alignment in each CM as well as between through multiple CMs

- 3 CM LINAC at 70 MeV/m
- Injected bunch of 1nC, 1.5 umrad, and 200 MeV
- Final beam energy 1.7 GeV

Bunch length (rms, $\mu\text{m}$ )	Off set ( $\mu\text{m}$ )	Relative emittance growth (%)
556	500	15
1112	200	13



# Introduction Staged Approach

- **Stage 3: Integrated Demonstration Towards the C<sup>3</sup> main LINAC**
  - The full stage 3 facility requires ~ 70m bunker.
  - The NLCTA will have to be extended by ~ 20m to host the full stage 3 LINAC.

Site	pros	cons
NLCTA at SLAC	continuation of Stage 1&2	needs extension of current bunker
IR12 at SLAC	ample space of existing tunnel with shielded large high bay area and control room on either side	these infrastructures were de-activated since the end of BarBar program. Will require investment to re-establish
FAST at Fermilab	well established operational accelerator infrastructure including cryogenic system	difficult to leverage the investment of Stage 1 and Stage 2
LINAC Extension Area (LEA) at ANL	ample footprint with reasonable infrastructure help to deepen synergy with AWA and APS	possibility for PWFA R&D is not yet clear

# Synergies and Impact

---

- ✓ Advanced accelerator concept study like staging PWFA

- ✓ Full energy linac injector for storage ring.

Stage 3: 3½ CM

- A 3 CM LINAC ~ 2.7 GeV reach over about 30 meters

- ✓ Independent energy tuning of beamlines in an x-ray FEL undulator farm

- ✓ Compact and cost-effective x-ray FEL.

Stage 2: 1½ CM

- A single CM linac with 8x50 MW klystrons of ~ 0.9 GeV over ~9 m

- ✓ Medical: VHEE therapy

- ✓ Compact high energy (100s keV to 1MeV) Compton source

- ✓ Lower energy injector for booster ring

- ✓ High brightness injector feasibility

Stage 1: ½ CM

- A half CM with 2x50MW klystrons – 0.32 GeV over 5 m

# Synergies and Impact

---

- ✓ Advanced accelerator concept study like staging PWFA
- ✓ Full energy linac injector for storage ring.

## Stage 3: 3½ CM

- A 3 CM LINAC ~ 2.7 GeV reach over about 30 meters
  - ✓ Independent energy tuning of beamlines in an x-ray FEL undulator farm
  - ✓ Compact and cost-effective x-ray FEL.

## Stage 2: 1½ CM

- A single CM linac with 8x50 MW klystrons of ~ 0.9 GeV over ~9 m
  - ✓ **Medical: VHEE therapy**
  - ✓ **Compact high energy (100s keV to 1MeV) Compton source**
  - ✓ **Lower energy injector for booster ring**
  - ✓ **High brightness injector feasibility**

## Stage 1: ½ CM

- **A half CM with 2x50MW klystrons – 0.32 GeV over 5 m**

# Synergies and Impact

---

- ✓ Advanced accelerator concept study like staging PWFA
- ✓ Full energy linac injector for storage ring.

## Stage 3: 3½ CM

- A 3 CM LINAC ~ 2.7 GeV reach over about 30 meters
  - ✓ Independent energy tuning of beamlines in an x-ray FEL undulator farm
  - ✓ Compact and cost-effective x-ray FEL.

## Stage 2: 1½ CM

- A single CM linac with 8x50 MW klystrons of ~ 0.9 GeV over ~9 m
  - ✓ Medical: VHEE therapy
  - ✓ Compact high energy (100s keV to 1MeV) Compton source
  - ✓ Lower energy injector for booster ring
  - ✓ High brightness injector feasibility

## Stage 1: ½ CM

- A half CM with 2x50MW klystrons – 0.32 GeV over 5 m

# Synergies and Impact

---

## Stage 3: 3½ CM

- ✓ Advanced accelerator concept study like staging PWFA
- ✓ Full energy linac injector for storage ring like CHSS injector (6GeV)
- A 3 CM LINAC ~ 2.7 GeV reach over about 30 meters
  - ✓ Independent energy tuning of beamlines in an x-ray FEL undulator farm
  - ✓ Compact and cost-effective x-ray FEL.


## Stage 2: 1½ CM

- A single CM linac with 8x50 MW klystrons of ~ 0.9 GeV over ~9 m
  - ✓ Medical: VHEE therapy
  - ✓ Compact high energy (100s keV to 1MeV) Compton source
  - ✓ Lower energy injector for booster ring
  - ✓ High brightness injector feasibility

## Stage 1: ½ CM

- A half CM with 2x50MW klystrons – 0.32 GeV over 5 m

# C<sup>3</sup>Demo Timeline



# Summary

---

- **The overall objective of this proposal is to mature** the RF and cryomodule technology and complete the beam dynamics investigation for the C<sup>3</sup> main LINAC.
  - design and analyze the main LINAC cryogenics
  - complete the design and construction of the cryomodules
  - demonstrate the accelerating structure with beam and wakefield damping
  - investigate the C<sup>3</sup> main LINAC machine and beam dynamics performance.
- **The C<sup>3</sup> Demonstration R&D Plan will**
  - provide key inputs for the conceptual design of the C<sup>3</sup> Higgs Factory.
  - open up significant new scientific and technical opportunities based on the C<sup>3</sup> accelerator technology.





# Thank you so much!

---

Questions?

