

# C<sup>3</sup> LINAC Demonstration Proposal

Cool Copper Collider Workshop, SLAC


---

Faya Wang

13 Feb. 2024



# Introduction Staged Approach

- C<sup>3</sup> accelerator technology: Modularized linac based on liquid N<sub>2</sub> cooled C-band cavity.
- Cryomodules (CM)s are vacuum insulated cryostats housing 4 rafts, and has 75 cm ID and about 9 m long.
- Rafts are mechanical supporting structures consisting of 2 accelerator structures and one quadrupole magnet. They are pre-aligned at 300K to 5 microns. Each raft has mechanical actuators to align one raft to the next with 5 degrees of freedom.



# RF Parameters – C<sup>3</sup>250/550 GeV

- At C<sup>3</sup> the same LINAC can deliver 250 GeV c.o.m and 550 GeV c.o.m in 8 km
- The optimized structure can reach 300 MΩ/m at 80K.
- The accelerator beam aperture (diameter) is 5.2 mm.




- Each CM can reach up to 0.7 GeV with 4 X 50MW klystrons .

Gradient (MV/m)	Power diss. (W)	rf flat top (ns)	Pulse compr.	Comments	Power/area (W/cm <sup>2</sup> )	ΔT Cu-bulk to LN <sub>2</sub> (K)
70	2500	700	N	C <sup>3</sup> -250	0.393	2.3
120	2500	250	N	C <sup>3</sup> -550	0.393	2.3
155	3900	250	N	C <sup>3</sup> -550 in 7 km	0.614	2.5
120	1650	250	Y	C <sup>3</sup> -550	0.259	2.1

# Introduction Staged Approach

- An X-band cryogenic structure has been demonstrated at high gradient.
- The C-band has been tested at low power at SLAC and high power without beam at Radiabeam
- **C<sup>3</sup> Linac Remaining Major Risks**
  - Achievable gradient and stability over C<sup>3</sup> full electron bunch train.
  - Beam emittance growth due to accelerator wakefields
  - Systematic study of alignment and vibration tolerance
  - Performance of the accelerators and the cryostat at the full cryogenic liquid and gas flow rate as expected in C<sup>3</sup>.
  - A reliable cost basis for extrapolation to C<sup>3</sup> scale production.



C<sup>3</sup> Demo will focus on the 5 thrusts:

- ❖ Collider Cryogenics Design Study
- ❖ CryoModule
- ❖ Accelerator Structure
- ❖ Beam Dynamics Experimental Study
- ❖ C<sup>3</sup> Main Linac Beam Dynamics Simulation Study

# Introduction Staged Approach

C<sup>3</sup> Demo will focus on the 5 thrusts:

❖ Collider Cryogenics Design Study


❖ CryoModule

❖ Accelerator Structure

❖ Beam Dynamics

❖ C<sup>3</sup> Main Linac Beam Dynamics

- Vibrations due to boiling of LN
- Large scale simulation setups (from 100s to 1000 meters)
- Optimizing CM and cold mass design to avoid the liquid surface turbulent flow
- Engineering procedures to eliminate possible problems from linac warm-up and cold-down process
- Instrumentation needs



# Introduction Staged Approach

C<sup>3</sup> Demo will focus on the 5 thrusts:


❖ Collider Cryogenics Design Study

❖ **CryoModule**

❖ Accelerator Structure

❖ Beam Dynamics

❖ C<sup>3</sup> Main Linac Beam Dynamics




- Adequate stability of the quadrupoles and accelerators during powered operation and full C<sup>3</sup> cryogenics fluid flow rate (with margins)
- Adequate range, precision and bandwidth of the raft positioning systems
- Full C<sup>3</sup> cryogenic flow rate benchmarking with simulation
- In-situ CM vibration measurement
- In-situ pre-beam alignment  $\leq 500$   $\mu\text{m}$
- Tunable permanent quadrupole magnets
- Waveguide transitions into the Cryomodule

# Introduction Staged Approach

C<sup>3</sup> Demo will focus on the 5 thrusts:

- ❖ Collider Cryogenics Design Study
- ❖ CryoModule
- ❖ **Accelerator Structure**
- ❖ Beam Dynamics
- ❖ C<sup>3</sup> Main Linac Beam Dynamics

- Achievable gradient and gradient stability at the C<sup>3</sup> equivalent beam loading
- HOM damping design and fabrication
- Integrated beam position monitor for structure alignment
- Optimization of the mechanical design for structure fabrication and tuning
- HOM detuning design






# Introduction Staged Approach

C<sup>3</sup> Demo will focus on the 5 thrusts:

- ❖ Collider Cryogenics Design Study
- ❖ CryoModule
- ❖ Accelerator Structure
- ❖ **Beam Dynamics**
- ❖ C<sup>3</sup> Main Linac Beam Dynamics

- Measure beam properties and validate wakefield model with simulations.
- Begin development of feedback loops for minimization of emittance growth.
- Develop systematic beam-based diagnostics for different stages of the Demonstrator.



# Introduction Staged Approach

---

C<sup>3</sup> Demo will focus on the 5 thrusts:

❖ Collider Cryogenics Design Study

❖ CryoModule


❖ Accelerator Structure

❖ Beam Dynamics

❖ C<sup>3</sup> Main Linac Beam Dynamics

- Perform emittance preservation simulation studies to determine alignment and vibration tolerances
- Investigation and optimization of lattice design, BNS damping, beam based alignment (1-1 steering, dispersion free steering, and wakefield corrections) ect.

# Introduction Staged Approach





# Introduction Staged Approach

---

- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - **Demonstrate the accelerator structure at the full C<sup>3</sup> equivalent beam loading:**
    - **Unloaded and loaded at 70 MeV/m and 700 ns with 190 mA – C<sup>3</sup>250**
    - **Unloaded and loaded gradient of 120 MeV/m and 250 ns with 300 mA - C<sup>3</sup>550**


# Introduction Staged Approach

- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - **Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading.**




# Introduction Staged Approach

- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - **Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading.**




## ✓ HCM Linac



- **2x50 MW C-band RF station needed to be developed.**
- **About 10% rf transmission loss**
- **With structure match to 43% beam loading**
  - 4 structure at 78 MeV/m with no beam
  - 2 structure at 111 MeV/m without beam and 90 MeV/m with 190 mA (C3-250)
  - 1 structure at 157 MeV/m without beam and 125 MeV/m with 300 mA (C3-550)

# Introduction Staged Approach


- **Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.**
  - Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading at SLAC NLCTA.
  - 2x50 MW C-band rf stations will be developed by repurposing an existing X-band station modulator.
  - The existing S-band station in NLCTA will be used to power the injector.




# Introduction Staged Approach

- Stage 1: Demonstration of C<sup>3</sup> Structure Performance at Full Beam Loading.

- Test a C<sup>3</sup> half Cryomodule (HCM) at full C<sup>3</sup> equivalent beam loading at SLAC NLCTA.





- $Q=115\text{pC}$ ,  $\gamma\epsilon_{x,y}$  (90%) =  $3.7 \times 3.3 \mu\text{m-rad}$
- 3 pC collimated on HCM aperture ( $r=2.6\text{mm}$ )





- Stage 1 will use NLCTA as it is.




# Introduction Staged Approach

---

- **Stage 2: First Scale-up Demonstration of A C<sup>3</sup> CryoModule Linac**
  - A high brightness photo injector with at least two bunches and various space
  - A large aperture S-band booster linac
  - A full C<sup>3</sup> CM Linac.
- Production of the cryomodule assembly with in-situ pre-beam alignment  $\leq 500 \mu\text{m}$
- Demonstration of the acceleration structure in the full CM LINAC reaching unloaded gradient of 155 MeV/m at 250 ns
- Development of high brightness RF photo injector with an LCLS-like S-band RF gun and an S-band booster LINAC re-using the Stage 1 HCM cryostat
- Evaluation of cryomodule LINAC beam performance in the presence of wakefields, and benchmarking with the beam simulation


# Introduction Staged Approach

- **Stage 2: First Scale-up Demonstration of A C<sup>3</sup> CryoModule Linac**
  - A high brightness photo injector with at least two bunches and variable bunch space
  - A large aperture S-band booster linac: repurpose the stage 1 half CM with 4x1m S-band structures
  - A full C<sup>3</sup> CM Linac.





# Introduction Staged Approach

- **Stage 2: First Scale-up Demonstration of A C<sup>3</sup> CryoModule Linac**
  - 8x50 MW C-band RF station will be built.
  - With zero beam loading (single electron bunch) and about 10% RF transmission loss
    - 1 klystron per structure: 8 structures at 113 MeV/m
    - 2 klystrons per structure: 4 structures at 160 MeV/m



# Introduction Staged Approach


- Stage 2: First Scale-up Demonstration of A C<sup>3</sup> CryoModule Linac
  - The preliminary simulation shows a 1nC beam of 2μm.rad emittance is possible at a final energy of 1.2 GeV.



# Introduction **Staged Approach**

- **Stage 2: First Scale-up Demonstration of a Full C<sup>3</sup> CryoModule**
  - **Beam diagnostics at the LINAC end: Long range wakefield and longitudinal short range wakefield**


Quantities	Devices
Energy and Energy spread	Dipole + screen/wire scanner
Charge	Faraday cup and beam dump, toroid
Beam size and beam position	Profile screens/wire scanner and NLCTA Quad package
Emittance and wakefield effects	Coherent undulator radiation and profile screen/wire scanner
Bunch length	Transverse deflecting cavity




# Introduction Staged Approach

- **Stage 2: First Scale-up Demonstration of a Full C<sup>3</sup> CryoModule**
  - **Beam diagnostics at the LINAC end: Long range wakefield and longitudinal short range wakefield**

Quantities	Devices
Energy and Energy spread	Dipole + screen/wire scanner
Charge	Faraday cup and beam dump, toroid
Beam size and beam position	Profile screens/wire scanner and NLCTA Quad package
Emittance and wakefield effects	Coherent undulator radiation and profile screen/wire scanner
Bunch length	Transverse deflecting cavity





PLAN VIEW  
END STATION "B"  
AND NLCTA HOUSING


NOTES:

THE NLCTA BEAMLINE GLOBAL COORDINATE SYSTEM IS DEFINED BY THE FOLLOWING



# Introduction Staged Approach

- **Stage 3: Integrated Demonstration Towards the C<sup>3</sup> main LINAC**
  - Cryogenics performance study at the C<sup>3</sup> full flow rate
  - Mapping out of transverse short range wakefield
  - Structure and magnet pre-beam alignment in each CM as well as between through multiple CMs




# Introduction Staged Approach

- **Stage 3: Integrated Demonstration Towards the C<sup>3</sup> main LINAC**
  - Cryogenics performance study at the C<sup>3</sup> full flow rate
  - Mapping out of transverse short range wakefield
  - Structure and magnet pre-beam alignment in each CM as well as between through multiple CMs

- 3 CM LINAC at 70 MeV/m
- Injected bunch of 1nC, 1.5 umrad, and 200 MeV
- Final beam energy 1.7 GeV

Bunch length (rms, $\mu\text{m}$ )	Off set ( $\mu\text{m}$ )	Relative emittance growth (%)
556	500	15
1112	200	13



# Introduction Staged Approach

- **Stage 3: Integrated Demonstration Towards the C<sup>3</sup> main LINAC**
  - The full stage 3 facility requires ~ 70m bunker.
  - The NLCTA will have to be extended by ~ 20m to host the full stage 3 LINAC.

Site	pros	cons
NLCTA at SLAC	continuation of Stage 1&2	needs extension of current bunker
IR12 at SLAC	ample space of existing tunnel with shielded large high bay area and control room on either side	these infrastructures were de-activated since the end of BarBar program. Will require investment to re-establish
FAST at Fermilab	well established operational accelerator infrastructure including cryogenic system	difficult to leverage the investment of Stage 1 and Stage 2
LINAC Extension Area (LEA) at ANL	ample footprint with reasonable infrastructure help to deepen synergy with AWA and APS	possibility for PWFA R&D is not yet clear

# Synergies and Impact

---

- ✓ Advanced accelerator concept study like staging PWFA

- ✓ Full energy linac injector for storage ring.

Stage 3: 3½ CM

- A 3 CM LINAC ~ 2.7 GeV reach over about 30 meters

- ✓ Independent energy tuning of beamlines in an x-ray FEL undulator farm

- ✓ Compact and cost-effective x-ray FEL.

Stage 2: 1½ CM

- A single CM linac with 8x50 MW klystrons of ~ 0.9 GeV over ~9 m

- ✓ Medical: VHEE therapy

- ✓ Compact high energy (100s keV to 1MeV) Compton source

- ✓ Lower energy injector for booster ring

- ✓ High brightness injector feasibility

Stage 1: ½ CM

- A half CM with 2x50MW klystrons – 0.32 GeV over 5 m

# Synergies and Impact

---

✓ Advanced accelerator concept study like staging PWFA

✓ Full energy linac injector for storage ring.

Stage 3: 3½ CM

- A 3 CM LINAC ~ 2.7 GeV reach over about 30 meters

✓ Independent energy tuning of beamlines in an x-ray FEL undulator farm

✓ Compact and cost-effective x-ray FEL.

Stage 2: 1½ CM

- A single CM linac with 8x50 MW klystrons of ~ 0.9 GeV over ~9 m

✓ **Medical: VHEE therapy**

✓ **Compact high energy (100s keV to 1MeV) Compton source**

✓ **Lower energy injector for booster ring**

✓ **High brightness injector feasibility**

**Stage 1: ½ CM**

- **A half CM with 2x50MW klystrons – 0.32 GeV over 5 m**

# Synergies and Impact

---

- ✓ Advanced accelerator concept study like staging PWFA
- ✓ Full energy linac injector for storage ring.

## Stage 3: 3½ CM

- A 3 CM LINAC ~ 2.7 GeV reach over about 30 meters
  - ✓ Independent energy tuning of beamlines in an x-ray FEL undulator farm
  - ✓ Compact and cost-effective x-ray FEL.

## Stage 2: 1½ CM

- A single CM linac with 8x50 MW klystrons of ~ 0.9 GeV over ~9 m
  - ✓ Medical: VHEE therapy
  - ✓ Compact high energy (100s keV to 1MeV) Compton source
  - ✓ Lower energy injector for booster ring
  - ✓ High brightness injector feasibility

## Stage 1: ½ CM

- A half CM with 2x50MW klystrons – 0.32 GeV over 5 m

# Synergies and Impact

---

## Stage 3: 3½ CM

- ✓ Advanced accelerator concept study like staging PWFA
- ✓ Full energy linac injector for storage ring like CHESS injector (6GeV)
- **A 3 CM LINAC ~ 2.7 GeV reach over about 30 meters**
  - ✓ Independent energy tuning of beamlines in an x-ray FEL undulator farm
  - ✓ Compact and cost-effective x-ray FEL.

## Stage 2: 1½ CM

- **A single CM linac with 8x50 MW klystrons of ~ 0.9 GeV over ~9 m**
  - ✓ Medical: VHEE therapy
  - ✓ Compact high energy (100s keV to 1MeV) Compton source
  - ✓ Lower energy injector for booster ring
  - ✓ High brightness injector feasibility

## Stage 1: ½ CM

- **A half CM with 2x50MW klystrons – 0.32 GeV over 5 m**

# C<sup>3</sup>Demo Timeline





# Summary

---

- **The overall objective of this proposal is to mature** the RF and cryomodule technology and complete the beam dynamics investigation for the C<sup>3</sup> main LINAC.
  - design and analyze the main LINAC cryogenics
  - complete the design and construction of the cryomodules
  - demonstrate the accelerating structure with beam and wakefield damping
  - investigate the C<sup>3</sup> main LINAC machine and beam dynamics performance.
- **The C<sup>3</sup> Demonstration R&D Plan will**
  - provide key inputs for the conceptual design of the C<sup>3</sup> Higgs Factory.
  - open up significant new scientific and technical opportunities based on the C<sup>3</sup> accelerator technology.



# Thank you so much!

---

Questions?

