

# Update on the C-band High Gradient Research Activities at LANL

Evgenya Simakov, Anna Alexander, Petr Anisimov, Walter C. Barkley, Torben Grumstrup, W. Brian Haynes, Dongsung Kim, Deepak Rai, Haoran Xu, MD Zuboraj

Los Alamos National Laboratory

02/12/2024

## **Outline of this talk**

- Introduction and LANL C-band project overview
- Status of high gradient cavity testing at CERF-NM
- Status of CARIE: the high gradient RF injector test facility
- Summary and near-term plans



## LANL High Gradient C-band research

#### The goals for LANL's high gradient project are

- To build a C-band (5.712 GHz) high gradient rf breakdown study facility (2019-2022).
- To build a C-band cryo-cooled photoinjector study facility (2022-2025).
- To conduct material studies.

This work was funded by Los Alamos National Laboratory (LANL) Laboratory Directed Research and Development (LDRD) program and Technology Evaluation and Development (TED) funds.





#### LANL C-band Engineering Research Facility (CERF-NM)

RESEARCH & DEVELOPMENT

## CERF-NM was built with \$3M of LANL's internal infrastructure investment.

- Powered with a C-band Canon klystron
- Conditioned to 50 MW
- Frequency 5.712 GHz

 $\bigotimes$ 

- 300 ns 1 µs pulse length
- Rep rate up to 200 Hz (typical 100 Hz)
- Nominal bandwidth 5.707-5.717 GHz





#### **NiCr absorbers for HOM suppression**

We conducted extensive optimizations of HOM suppression in a 20-cell C-band accelerating structure with NiCr absorbers.





#### **Two-cell test cavity with NiCr absorbers**

- A two-cell cavity was designed to test if a structure with NiCr aborbers can be conditioned to high gradients.
- Issues to be studied: pulse heating, HOM generation during breakdown.



#### **Various HOMs**



#### **Fabrication of the cavity with absorbers**

The cavity will be fabricated in four quadrants and several steps:

- Pre-fabrication of quadrants with HOM damping manifolds.
- Deposition of Ni and Cr layers.
- Fabrication of all cavity features that will remove unwanted NiCr layer.
- Final brazing and heat treatment of NiCr.





#### Summary and test plans for the cavity with NiCr absorbers

- Design of the cavity with NiCr absorbers is complete.
- Procurement is complete. Fabrication started in Dymenso.
- Delivery is expected in August of 2024 followed by testing at CERF-NM.



#### **CARIE: Cathodes And Rf Interactions in Extremes**

A new three-year project was funded at LANL to demonstrate operation of high-quantum-efficiency cathodes in a high-gradient RF injector.

- Project builds upon LANL's expertise in highgradient C-band and high-QE photocathodes.
- The proposed heterostructured cathode will include multiple layers to ensure atomic flatness of the surface, high QE, and the ability to withstand high electric fields with no breakdown.
- Target beam parameters: 250 pC, 0.1  $\mu$ m\*rad, B<sub>5D</sub> = 10<sup>16</sup> A/m<sup>2</sup>.
- The project started in October of 2022.





#### **CARIE** vault

- A location was identified on LANSCE mesa that can accommodate a 20 kW electron beam.
- The vault was cleaned for the new experiment.
- A modulator for the 50 MW C-band klystron has finally arrived.
- The klystron is installed. Conditioned to 35 MW of the output power, 1.5 µs pulse width, 50 Hz rep rate.





#### **CARIE** vault facility lineout – design with a magic T



### **50 MW power circulator for CARIE**

- Fabricated by Microwave Techniques LLC.
- Received at LANL in January, 2024.
- Designed to operate at 50 MW of power, 1 µs pulse, 100 Hz repetition rate.
- Must be filled with SF6 at 55 psi.
- Problem: CML WR187 windows are designed for 40 psi, Microwave Techniques WR187 windows are designed for 35 psi.
- Microwave Techniques states that if filled to 30 psi, should operate up to 10 MW of power.

RESEARCH & DEVELOPMEN





2/8/2024

#### **CARIE** vault facility lineout – design a circulator

• Installation is currently in progress.



2/8/2024

#### **RF** photoinjector electromagnetic design

- RF design for the all-copper photoinjector is complete.
- 1.6 cell injector •
- Two waveguides couple the half-cell and the full cell with 180<sup>0</sup> phase advance.
- $E_{surf}/E_{cath}$ =1.28,  $H_{surf}Z_0/E_{cath}$ =0.64. ٠
- Power for  $E_{cath}$  = 240 MV/m is about 8 MW.





15

70000

60000

40000

30000

20000 10000

0

10

#### **RF photoinjector fabrication**

- We will first fabricate and test an all-copper injector with no cathode plug.
- CAD design for the allcopper photoinjector is complete.
- The cavity was received at LANL in October, 2023.





2/8/2024

### **RF photoinjector cold testing**

- Tuning of the photoinjector was successful.
- Tuned frequency 5710.53 MHz in air (5712.15 MHz in vacuum).
- Measured Q-factor 11869 (computed Qfactor 11934).









#### **Field profile measurement**

- Good agreement with CST after tuning on 11/14/2023.
- Cathode field is 95% of the field in full cell.





2/8/2024

#### Photoinjector with a cathode plug

- CARIE facility will be used to study behavior of cathodes at high gradient.
- INFN-style cathode plug will be used for inserting cathodes.
- The choke cavity will reject the fundamental mode coupling into the plug insertion hole.



2/8/2024

#### Thoughts on the cathode plug positioning accuracy...



CST simulation of the field profile for different cathode plug positions:



**Micron-scale** alignment tolerance is required, between the photocathode surface and the cathode-cell plane.

2/8/2024

## LANL has plans for further developing its C-band accelerator capabilities

RESEARCH & DEVELOPME

- Director Initiative money were allocated in FY22 to jump start this facility.
- 5-year goal: build operational C-band cryocooled copper accelerator.
- Ultimate goal: provide 43 keV and 100 keV photon bursts for material studies with Inverse Compton Scattering
- Another project idea under development MeV Ultrafast Electron Diffraction facility.





2/8/2024