



## Design of the PIP-II Tunnel Geodetic Control Network

David Krawczuk

International Workshop on Accelerator Alignment 2024 (IWAA 2024)


October 2024 (Updated November 2024)

# Overview

- **Introduction**
- Technical Requirements
- Network Design
- Network Results
- Network Verification
- Conclusion

## Introduction

- Proton Improvement Plan II
- 215-meter long Linac will accelerate protons up to 800 MeV
- Beam will then transported through Beam Transfer Line (BTL)
- Beam will finally inject into Booster
- Main sections
  - Warm front-end (HBB)
  - SRF Linac
  - Beam Transfer Line (BTL)
  - Total length ~ 550 m



# Overview

- Introduction
- **Technical Requirements**
- Network Design
- Network Results
- Network Verification
- Conclusion

## General Tolerance Requirements

- All values in this presentation are shown to  $1\sigma$  confidence level
- The Alignment Network shall provide a single-point absolute measurement accuracy of 0.50mm RMS relative to the FSCS-Z absolute frame
- The Alignment Network shall provide a relative measurement accuracy of 0.25mm RMS between points separated by <100m, relative to a local frame
- The Alignment Network shall support the combined alignment tolerances specified in the misalignment tolerances document

## Component Tolerance Requirements

- The total RMS value of all the error components added quadratically shall not exceed the placement requirements
- Placement requirements were based on multiparticle simulations
- Based on the requirement that the beam can propagate through the **whole SRF Linac (~ 175 m)** with a high probability with specified errors **without orbit correction**
- For network verification, this requirement was extended for the entire beamline (~ 550 m) for thoroughness

# Cold Component Tolerance Requirements

	Trans.	Vert.	Long.			
Beam Line Element	X-Offset (mm)	Y-Offset (mm)	Z-Offset (mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
<b>Cavities</b>						
HWR Cavity	0.5	0.5	1	3	3	NR
SSR1 Cavity	0.5	0.5	1	3	3	NR
SSR2 Cavity	0.5	0.5	1	3	3	NR
LB650 Cavity	0.5	0.5	1	2	2	NR
HB650 Cavity	0.5	0.5	1	1	1	NR
<b>Solenoids</b>						
Solenoid HWR*	0.5	0.5	1	1	1	5
Solenoid SSR1*	0.5	0.5	1	1	1	5
Solenoid SSR2*	0.5	0.5	1	1	1	5
<b>Cold Instrumentation</b>	<b>X-Offset (mm)</b>	<b>Y-Offset (mm)</b>	<b>Z-Offset (mm)</b>	<b>Pitch (mrad)</b>	<b>Yaw (mrad)</b>	<b>Roll (mrad)</b>
Cold BPMs	0.5	0.5	1	F	F	5*



## Warm Component Tolerance Requirements (1/2)

Beam Line Element	X-Offset (mm)	Y-Offset (mm)	Z-Offset (mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
<b>Front End</b>						
Ion source	0.25	0.25	5	<i>F</i>	<i>F</i>	<i>NR</i>
LEBT Solenoid	0.25	0.25	5	<i>F</i>	<i>F</i>	40
LEBT Dipole Magnet	0.25	0.25	5	<i>F</i>	<i>F</i>	<i>F</i>
LEBT Chopper	0.25	0.25	5	<i>F</i>	<i>F</i>	<i>NR</i>
RFQ entrance/exit	0.125	0.125	2	<i>F</i>	<i>F</i>	1
MEBT Quad	0.25	0.25	0.5	<i>F</i>	<i>F</i>	4
MEBT Corrector	1	1	0.5	<i>F</i>	<i>F</i>	4
Bunching cavities	0.175	0.175	1	<i>F</i>	<i>F</i>	<i>NR</i>
200 Ohm Kicker	0.25	0.05	0.25	<i>F</i>	<i>F</i>	<i>F</i>
MEBT Absorber	1	0.125	1.5	0.25	2	5
Differential Pumping Insert	0.25	0.25	5	1	1	<i>NR</i>
<b>SRF Linac</b>						
RT Linac Quad	0.25	0.25	0.5	<i>F</i>	<i>F</i>	3
RT Steering Dipole	1	1	1	10*	<i>F</i> *	5
Straight Ahead Dump	1	1	5	5	5	<i>NR</i>



## Warm Component Tolerance Requirements (2/2)

BTL						
RT BTL Quad	0.25	0.25	0.5	<i>F</i>	<i>F</i>	3
RT BTL Dipole	0.25	0.25	0.5	<i>F</i>	<i>F</i>	2
RT Steering Dipole	1	1	1	10*	<i>F</i> *	5
BTL Septum	0.25	0.25	0.5	<i>F</i>	<i>F</i>	3
BTL Switch Dipole	0.25	0.25	0.5	<i>F</i>	<i>F</i>	3
BTL Beam Absorber	1	1	5	5	5	<i>NR</i>
Beam Line Element	X-Offset (mm)	Y-Offset (mm)	Z-Offset (mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
Faraday Cup	0.5	0.5	0.5	<i>NR</i>	<i>NR</i>	<i>NR</i>
Fast Faraday Cup	0.5	0.5	0.5	3	3	<i>NR</i>
LEBT Allison Scanner	1	1	1	5*	5*	5
MEBT Allison Scanner	1	1	1	1*	3*	5
RT BPM	0.25	0.25	0.5	<i>F</i>	<i>F</i>	5
Laser Wire	0.25	0.25	0.25	<i>F</i>	<i>F</i>	5
Wire scanner	0.5	0.5	0.5	<i>F</i>	<i>F</i>	5
Scraper	0.25	0.25	0.25	3	3	3
ACCT	0.5	0.5	0.5	<i>NR</i>	<i>NR</i>	<i>NR</i>
DCCT	0.5	0.5	0.5	<i>NR</i>	<i>NR</i>	<i>NR</i>
RWCM	0.5	0.5	0.5	<i>NR</i>	<i>NR</i>	<i>NR</i>
Longitudinal pickup	0.5	0.5	0.5	<i>NR</i>	<i>NR</i>	<i>NR</i>

# Overview


- Introduction
- Technical Requirements
- **Network Design**
- Network Results
- Network Verification
- Conclusion

# Surface Network - Overall






# Surface Network - Detail






# Tunnel Network - Overall



# Tunnel Network – Control Point Placement



# Control Points and Instrument Specifications

- Kyjak Bolt



- Instrument Uncertainties

Instrument Type	Instrument Model	Uncertainties
Laser Tracker	Leica AT401/AT403	$\sigma_{Hz,V} = 1''$ , $\sigma_a = 0.008 \text{ mm}$ , $\sigma_b = 2.5 \text{ ppm}$
Digital Level	Leica DNA03	$\sigma_a = 0.050 \text{ mm}$ , $\sigma_b = 2 \text{ ppm}$
Total Station	Leica TS60	$\sigma_{Hz,V} = 0.5''$ , $\sigma_a = 0.600 \text{ mm}$ , $\sigma_b = 1 \text{ ppm}$



## Pre-Analysis Details (1/2)

- 621 control points
- 52 laser tracker/Digital Level Setups
  - Trackers and levels collocated for convenience
  - Should approximate elevation measurements to a reasonable level
- 8 total station setups
- 1257 laser tracker/digital level observations
  - Slope Distance
  - Horizontal Direction
  - Vertical Angle
  - Rod Reading
- 56 total station observations
  - Slope Distance
  - Horizontal Direction
  - Vertical Angle

## Pre-Analysis Details (2/2)

- Weighted Constraints
  - 5 sight-riser points
  - 31 points in the High Bay Building (HBB)
  - 24 Booster points
- Constrained Point Uncertainties
  - HBB and Booster uncertainties unavailable
  - Method 1: Surface Network Uncertainty + Transfer Uncertainty (2D)
    - Sight-Riser Surface Network Points (Single Component): 0.218 mm
    - Transfer Uncertainty (Wild NL, Single Component): 0.250 mm for 10-meter drop
    - Quadrature (Single Component): 0.332 mm
  - Method 2: 2006 Tevatron Network Adjustment Results (3D)
    - $\sigma_x = 0.325$  mm,  $\sigma_y = 0.315$  mm,  $\sigma_z = 0.315$  mm
  - **Decision:  $\sigma_x = \sigma_y = \sigma_z = 0.325$  mm**

# Overview

- Introduction
- Technical Requirements
- Network Design
- **Network Results**
- Network Verification
- Conclusion

## Pre-Analysis Results (1/2)


- 3D uncertainties calculated using error propagation
- Custom Python program
  
- Results

Station Uncertainties	Hz (2D) / V (1D), mm
Mean Absolute	0.152 / 0.055
Max Absolute	0.210 / 0.069
Mean Relative (< 100 m)	0.105 / 0.030
Max Relative (< 100 m)	0.212 / 0.067


- Meets absolute accuracy requirements of 0.500 mm
- Meets relative accuracy requirements of 0.250 mm

# Pre-Analysis Results (2/2)

Results (Only LT/DL Shown)



Results (Only TS Shown)



# Overview

- Introduction
- Technical Requirements
- Network Design
- Network Results
- **Network Verification**
- Conclusion

## Network Verification

- Need to verify that the quadrature of global and local errors can meet alignment tolerance requirements
- Global errors
  - Network uncertainty
- Local errors (metrology)
  - Noise in metrology measurements
  - Stand adjustment errors





## Global Errors – Network Uncertainty (2/2)

- Used the following algorithm on all 52 laser tracker positions
  - Identify all control points measured from instrument
  - Create VCV submatrix of only the measured control points from full network VCV matrix
  - Propagate measured control point errors through best-fit transformation
  - Compute uncertainties in transformation parameters
- Results

Cold & Warm					
X (trans., mm)	Y (vert., mm)	Z (long., mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
0.201	0.057	0.168	0.008	0.009	0.004

Warm – Front End					
X (trans., mm)	Y (vert., mm)	Z (long., mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
0.078	0.048	0.056	0.001	0.004	0.001


## Local Errors

- Local error sources
  - Fiducial positions
  - Component electrical center positions
  - Mechanical feature positions (ex: flange centers, stud positions, etc.)
- Focused on fiducial positions only due to time constraints
- Should still provide a reasonable estimate for verification purposes


## Local Errors

- Cold Component Analysis
  1. Individual component alignment on strongback
  2. Component string & strongback insertion into vacuum vessel
  3. Vacuum vessel placement inside tunnel
- Warm Component Analysis
  - Direct placement of component in tunnel only
- Picked a basic model due to time constraints
  - Dimensions chosen to best represent all components


# Model



# Component Alignment to Strongback




# Component String/Strongback Insertion to Vacuum Vessel





# Placement of Vacuum Vessel Inside Tunnel



## Local Errors – Measurement Noise

- Laser tracker measurement uncertainty
  - Used instrument uncertainty analysis function in SpatialAnalyzer
  - Computed uncertainties on component/strongback/vessel fiducials
- Best-fit transformation uncertainties for cold components
  - Error stack-up from repeated best-fits
    - Component string/strongback insertion to vacuum vessel
    - Placement of vacuum vessel inside tunnel
  - Used custom Python best-fit transformation error propagation program
  - Input: fiducial uncertainties
  - Output: final component alignment uncertainties inside tunnel

## Local Errors – Measurement Noise Results

- Cold components

X (trans., mm)	Y (vert., mm)	Z (long., mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
0.006	0.007	0.005	0.009	0.009	0.008

- Warm component uncertainties would be even less significant
  - Assumed to be same as cold components for convenience

## Local Errors – Stand Adjustment Error

- Adjustment stands keep components in place
- Component position adjusted by finely threaded bolts or studs on stands
- Mechanical limitations on adjustability
- Practical limit for each fiducial:  $\pm 0.100$  mm
  - Based on previous experience
- Estimated alignment uncertainties using Monte Carlo simulations

# Local Errors – Stand Adjustment Error – Monte Carlo

- Custom Python program
- Algorithm
  1. Generate shift errors and orientation errors using uniform distribution
  2. Check if all fiducials are  $< 0.100$  mm
  3. If so, move on to next step
    1. Individual component alignment on strongback
    2. Component string & strongback insertion into vacuum vessel
    3. Vacuum vessel placement inside tunnel

## Local Errors – Stand Adjustment Error Results

- Cold components

X (trans., mm)	Y (vert., mm)	Z (long., mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
0.103	0.080	0.085	0.138	0.141	0.145

- Warm components

X (trans., mm)	Y (vert., mm)	Z (long., mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
0.050	0.055	0.042	0.133	0.148	0.117

# Network Verification Results (Quadrature Calculation)

Cold	X (trans., mm)	Y (vert., mm)	Z (long., mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
Global - Network	0.201	0.057	0.168	0.008	0.009	0.004
Local - Noise	0.006	0.007	0.005	0.009	0.009	0.008
Local - Stand	0.103	0.080	0.085	0.138	0.141	0.145
<b><u>Total</u></b>	<b><u>0.226</u></b>	<b><u>0.098</u></b>	<b><u>0.188</u></b>	<b><u>0.139</u></b>	<b><u>0.142</u></b>	<b><u>0.145</u></b>

Warm	X (trans., mm)	Y (vert., mm)	Z (long., mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
Global - Network	0.201	0.057	0.168	0.008	0.009	0.004
Local - Noise	0.006	0.007	0.005	0.009	0.009	0.008
Local - Stand	0.050	0.055	0.042	0.133	0.148	0.117
<b><u>Total</u></b>	<b><u>0.207</u></b>	<b><u>0.080</u></b>	<b><u>0.173</u></b>	<b><u>0.134</u></b>	<b><u>0.149</u></b>	<b><u>0.117</u></b>

Warm – Front End	X (trans., mm)	Y (vert., mm)	Z (long., mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
Global - Network	0.078	0.048	0.056	0.001	0.004	0.001
Local - Noise	0.006	0.007	0.005	0.009	0.009	0.008
Local - Stand	0.050	0.055	0.042	0.133	0.148	0.117
<b><u>Total</u></b>	<b><u>0.093</u></b>	<b><u>0.073</u></b>	<b><u>0.070</u></b>	<b><u>0.133</u></b>	<b><u>0.148</u></b>	<b><u>0.117</u></b>

## Network Verification Results

- All alignment tolerances are expected to be met except for one warm component
  - 0.073 mm > 0.050 mm

	<b>Trans.</b>	<b>Vert.</b>	<b>Long.</b>			
Beam Line Element	X-Offset (mm)	Y-Offset (mm)	Z-Offset (mm)	Pitch (mrad)	Yaw (mrad)	Roll (mrad)
<b>Front End</b>						
200 Ohm Kicker	0.25	0.05 <b>X</b>	0.25	<i>F</i>	<i>F</i>	<i>F</i>

- Can be accounted for by beam-based alignment
- Differential corrections can be applied using precise methods
  - Micrometer < 0.050 mm
  - Interferometer < 0.050 mm



# Overview

- Introduction
- Technical Requirements
- Network Design
- Network Results
- Network Verification
- **Conclusion**

## Conclusion

- Absolute and relative network tolerances are expected to be met
- All alignment tolerances are expected to be met except for one warm component
  - Can be accounted for by beam-based alignment

# Acknowledgements

- I would like to sincerely thank the following people for assisting me in this project
- Technical Review
  - Dr. Virgil Bocean
  - John Kyle
  - Georg Gassner (SLAC)
- Technical Feedback
  - Charles Wilson
  - Curtis Baffes
- Surface Network Pre-Analysis Data
  - John Kyle
  - Jana Barker (now DESY)

Thank you!

